

ARDMORE PUBLIC WORKS AUTHORITY

Authority Letter No. 5617
Meeting Date February 21, 2023

Ardmore Public Works Authority
City of Ardmore, Oklahoma

Re: Request to approve Work Order No.2 received from
Insituform for the repair and rehab of sewer lines and
manholes.

Dear Trustees:

Staff is requesting to approve Work Order No. 2 received from Insituform based on their 2022 Maintenance Contract unit pricing for the repair and rehab of sewer lines and manholes behind the Valero Refinery in the amount of \$1,391,571.50. This project is funded in the current Sewer Collection Department Budget.


Staff recommends the approval of Work Order No. 2 received from Insituform for the repair and rehab of sewer lines and manholes from the Highway 142 overpass to behind Atlas Roofing in the amount of \$1,391,571.50.

Sincerely,



Shawn Geurin, Utilities Director

Reviewed by: _____


APWA Manager

2022 Maintenance Contract - Interceptors
W02

Item	Description	Qty	Unit	Unit Price	Extended
1	Travel & mobilization - CCTV	1	EA	\$7,500.00	\$7,500.00
2	Travel & mobilization - CIPP	1	EA	\$7,500.00	\$7,500.00
3	Travel & mobilization - Excavation Crew	1	EA	\$7,500.00	\$7,500.00
4	24" TV/Clean sanitary sewer	4539	LF	\$15.00	\$68,085.00
5	Root removal	2000	LF	\$3.50	\$7,000.00
6	Other Remote Obstruction Removal (max 10 LF)	50	EA	\$750.00	\$37,500.00
7	Tuberculation Removal	5400	IN/DIA/LF	\$4.00	\$21,600.00
8	15" x 7.5mm CIPP	582	LF	\$65.00	\$37,830.00
9	24" x 10.5mm CIPP	5017	LF	\$124.00	\$622,108.00
10	15"-21" CIPP Setup charge per install length	582	LF	\$18.00	\$10,476.00
11	24"-36" CIPP Setup charge per install length	5017	LF	\$23.00	\$115,391.00
12	Non-Standard Resin System Add-On (VE for Aerials)	9437	IN/DIA/LF	\$12.00	\$113,244.00
13	6"-18" Post TV after rehabilitation	582	LF	\$2.00	\$1,164.00
14	21"-36" Post TV after rehabilitation	5017	LF	\$3.00	\$15,051.00
15	Setup 8" Pump	3	EA	\$750.00	\$2,250.00
16	Operate 8" Pumping System	26	Day	\$2,250.00	\$58,500.00
17	Setup 12" Piping	2922	LF	\$50.00	\$146,100.00
18	Install New 4' DIA Manhole 0'-6' deep	1	EA	\$7,000.00	\$7,000.00
19	New Manhole Frame & Cover	1	EA	\$1,200.00	\$1,200.00
20	Trench safety	10	LF	\$10.00	\$100.00
21	Granular backfill	20	TON	\$55.00	\$1,100.00
22	Clearing/grubbing for Access	1.5	Acre	\$7,500.00	\$11,250.00
23	15" & 18" Additional 1.5mm	399	LF	\$14.50	\$5,785.50
24	21" & 24" Additional 1.5mm	1796	LF	\$15.75	\$28,287.00
CO1.1	Heavy Grading using on-site material up to 20 tons crushed rock MH 4574-4575	1	LS	\$9,200.00	\$9,200.00
CO1.2	Light Grading using on-site material MH 4550,4553,4554	1	LS	\$9,500.00	\$9,500.00
CO1.3	Remove & Replace MH Cones (4605)	1	EA	\$8,750.00	\$8,750.00
CO1.4	Light Grading using on-site material MH 4605	1	LS	\$3,400.00	\$3,400.00
CO1.5	Heavy Grading using on-site material up to 20 tons crushed rock MH 4607,4608,4609	1	LS	\$9,800.00	\$9,800.00
CO1.6	Medium Grading using on-site material MH 4603	1	LS	\$6,300.00	\$6,300.00
CO1.7	Heavy Grading using on-site material up to 20 tons crushed rock MH 4585-4586	1	LS	\$11,100.00	\$11,100.00

\$1,391,571.50